

Artificial Readymade Building

Rupesh Kumar¹, Ashish Verma², Sanjay Maurya³, Bhism⁴,
Sampurna Nand⁵, Rahul Yadav⁶

¹³⁴⁵⁶Student, Buddha institute of Technology,(Gkp, U.P., INDIA)

²Asst.Prof, Buddha institute of Technology,(Gkp, U.P., INDIA)

Submitted: 15-07-2021

Revised: 29-07-2021

Accepted: 31-07-2021

ABSTRACT

Now in a modern days conventional type of construction is fading up as compared to Artificial Readymade Building type construction . Precast concrete is a smart way to build any type of building, safely, affordably. It ensures fast construction time, high profitability and excellent quality . Precast concrete is an industrialized way to build. It means transfer of work from sites to factories. This improves productivity and quality and shoertens construction time of a building. Inshort, precast concrete lowers total construction costs considerably. This paper deals with the study of Precast technology, artificial way of construction and its advantages over Conventional way of construction.

Construction plays a very important role in economic growth through the multiple effects on the other sectors of the country's economy. Artificial Readymade Building construction concept include those structures where the majority of structural components are standardized and produced in plants or yards in a location nearer or away from the construction site, and transported to the site location for its assembly. The standardized precast elements facilitate mass production, in order to build large number of buildings in short duration. Artificial Readymade Building construction method has been adopted as the moulds of standardized components facilitates mass production with stringent quality control. Precast construction method involves setting up of casting yard, production & stacking, transportation and erection of precast building elements. Artificial Readymade Building is effective in terms of time, labours requirement, superior quality, better performance & finish, optimal material requirement, less wastage, reduced use of shuttering, desired shape, better finish etc., It is convenient to establish precast yard and to erect the precast elements at (near) site which speeds up the process & contributes towards mitigating delays in large scale construction projects. As this method

requires skilled group of people.

Keyword:-, Artificial readymade building, precast construction ,precast concrete, precast

I. INTRODUCTION

Artificial Readymade building uses precast concrete as a construction product produced by casting concrete in a reusable mold or form which is then cured in a controlled environment , transported to the construction site and erected into place. Indian realty majors are adopting precast technology in building their latest projects.

The main advantages of Artificial Readymade building technology are quality, speed of construction and a value for money product. To avoid labour shortage, time delays and with an aim to deliver quality products, developers and builders are now adopting precast technology. The use of such technology helps in upto to 60% of the time taken for similar projects using normal construction methods and technology. In other words if normal brick and mortar method takes one year to complete a project, the precast method takes about three to four months. Artificial Readymade Building technology has proved its worth by saving a lot of construction time in the Europe and the Middle East.The best part of the technology is that it not only speeds up the construction work but also enhances the quality of final work.

INTRODUCTION

The concept of precast (also known as "prefabricated") construction includes those buildings where the majority of structural components are standardized and produced in plants in a location away from the building, and then transported to the site for assembly. These components are manufactured by industrial methods based on mass production in order to build a large number of buildings in a short time at low cost.

The main features of this construction process are

as follows:

- The division and specialization of the human workforce
- The use of tools, machinery, and other equipment, usually automated, in the production of standard, interchangeable parts and products

This type of construction requires a restructuring of the entire conventional construction process to enable interaction between the design phase and production planning in order to improve and speed up the construction. One of the key premises for achieving that objective is to design buildings with a regular configuration in plan and elevation. Urban residential buildings of this type are usually five to ten stories high. Many countries used various precast building systems during the second half of the 20th century to provide low-income housing for the growing urban population. They were very popular after the Second World War, especially in Eastern European countries and former Soviet Union republics. In the former Soviet Union, different precast buildings systems are denoted as “Seria,” whereas in Romania they are called “Secțiunea.”

In general, precast building systems are more economical when compared to conventional multifamily residential construction (apartment buildings) in many countries.

History of Precast Technology

Ancient Roman builders made use of concrete and soon poured the material into moulds to build their complex network of aqueducts, culverts, and tunnels. Modern uses for pre-cast technology include a variety of architectural and structural applications — including individual parts, or even entire building systems. In the modern world, precast panelled buildings were pioneered in Liverpool, England, in 1905. The process was invented by city engineer John Alexander Brodie, a creative genius who also invented the idea of the football goal net. The tram stables at Walton in Liverpool followed in 1906. The idea was not taken up extensively in Britain. However, it was adopted all over the world, particularly in Eastern Europe[4] and Scandinavia. In the US, precast concrete has evolved as two subindustries, each represented by a major association.

The precast concrete products industry focuses on utility, underground and other non-prestressed products, and is represented primarily by the National Precast Concrete Association (NPCA). The precast concrete structures industry focuses on prestressed concrete elements and on

other precast concrete elements used in above-ground structures such as buildings, parking structures, and bridges. This industry is represented primarily by of the Precast/Prestressed Concrete Institute (PCI).

COST FACTOR

The cost of construction with this technology is marginally higher than the conventional method, theoretically but on practical consideration when we consider the wastage control and speed of construction with best quality and with virtually no repair or reworking cost, it works out to the same value and eventually the clients will get much superior product on the same amount of investment.

TYPE OF ARTIFICIAL READYMADE BUILDING SYSTEM

Depending on the load bearing structure artificial readymade building systems can be divided into the following categories:

- (a) Large panel systems
- (b) Frame systems
- (c) Slab column systems with wall
- (d) Mixed system

(a) Large Panel System :

This system refers to multi storey structures composed of large walls and floor concrete panels connected in the vertical and horizontal directions so that the wall panels enclose appropriate spaces for the rooms with a building . These panels form a box like structure. Both horizontal and vertical panels resist gravity loads.

(b) Frame Structure:

Precast frames can be constructed using either linear elements or spatial beam-column sub assemblages. Precast beam-column sub-assemblages have the advantages that the connecting faces between the sub-assemblages can be placed away from the critical frame regions; however linear elements are generally preferred because of the difficulties associated with forming, handling and erecting spatial elements.

(c) Slab-Column system with Shear wall:

These systems rely on shear walls to sustain lateral load effects, where as the slab-column structure resists mainly gravity loads. There are two main systems in this category:

- (i) Lift slab system with walls : In this system, the load bearing structure consists of precast reinforcement concrete columns and slabs. Precast columns are usually two stories high. All precast structural elements are assembled by means of special joints.
- (ii) Pre stressed slab-column system:

Inprestressed slab-column system uses horizontal prestressing in two orthogonal directions to achieve continuity. The precast column elements are 1 to 3 stories high. The reinforcement concrete floor slabs fit the clear span between columns.

Following are some elements of Precast

- (1) Precast Slabs
- (2) Precast Beam and Girders
- (3) Precast Columns
- (4) Precast Walls
- (5) Precast Stairs.

II. METHODOLOGY

Artificial readymade building process has been adopted as the moulds of standardized components facilities mass production with stringent quality control. Artificial readymade building process involves setting up of casting yard, production and stacking, transportation and erection of precast elements .

Artificial readymade building process has been adopted as the moulds of standardized components facilities mass production with stringent quality control. Artificial readymade building process involves setting up of casting yard, production and stacking, transportation and erection of precast elements .

BASIC DESIGN CONCEPTS FOR ARTIFICIAL READYMADE CONCRETE BUILDING

- (1) In design of precast members and connections, all loading and restraint conditions from casting to end use of the structure should be considered. The stresses developed in precast elements during the period from casting to final connection may be more critical than the service load stresses. Special attention should be given to the methods of stripping, storing, transporting, and erecting precast elements.
- (2) When precast members are incorporated into a structural system, the forces and deformations occurring in and adjacent to connections (in adjoining members and in the entire structure) should be considered. The structural behavior of precast elements may differ substantially from that of similar members that are monolithically cast in place. Design of connections to transmit forces due to shrinkage, creep, temperature change, elastic deformation, wind forces, and earthquake forces require special attention. Details of such

connections are especially important to insure adequate performance of precast structures.

- (3) Precast members and connections should be designed to meet tolerance requirements. The behavior of precast members and connections is sensitive to tolerances. Design should provide for the effects of adverse combinations of fabrication and erection tolerances. Tolerance requirements should be listed on contract documents, and may be specified by reference to accepted standards. Tolerances that deviate from accepted standards should be so indicated.
- (4) All details of reinforcement, connections, bearing elements, inserts, anchors, concrete cover, openings and lifting devices, and specified strength of concrete at critical stages of fabrication and construction, should be shown on either the contract documents prepared by the architect/engineer of record or on the shop drawings furnished by the contractor. Whether this information is to be shown on the contract documents or shop drawings depends on the provisions of the contract documents. The shop drawings should show, as a minimum, all details of the precast concrete members and embedded items

The contract documents may specify that portions of connections exterior to the member are also to be shown on the shop drawings. The contract documents may also require the contractor to provide designs for the members and/or connections. The contract documents should show the loads to be considered in design of the precast concrete elements of the structure, and they should indicate any special requirements or functions (for example: seismic loads, allowance for movements, etc.) that should be considered in design assigned to the contractor. In this case, the shop drawings should include complete details of the connections involved.

Advantages Of Artificial Readymade Building Construction Over Conventional Construction

- (1) Since precast is manufactured in a controlled casting environment it is easier to control the mix, placement and curing.
- (2) Since a precaster can buy material for multiple projects quality discounts can lower cost.
- (3) Quality can be controlled and monitored much more easily.
- (4) Less labour is required and that labour can be less skilled.



Fig: ARTIFICIAL READYMADE BUILDING

III. CONCLUSION

- (1) Precast has lower lifetime costs than any other building solution.
- (2) Precast minimizes structural maintenance needs during years.
- (3) Applications of precast concrete structural systems for the construction of low-cost apartments have gained vast progress worldwide and so to speak in Indonesia as well. This is due to the fact that precast concrete systems have several advantages compared to the conventional cast-in-situ concrete system.
- (4) It was found that structural construction cost efficiency around 5-10% was generally obtained by replacing conventional structural system with precast concrete.
- (5) It has also been proved that the construction speed was able to be increased significantly in-line with the achievement of better quality works and more eco-friendly construction projects.
- (6) The use of precast concrete as structural components will definitely enhance in the

future.

- (7) The precast concrete technology has already arrived in India due to large size projects, need for quality construction with speed and reduced labour force.

All these advantages can be exploited to the maximum by careful planning and designing.

REFERENCES

- [1] Precast concrete – Wikipedia
- [2] https://en.wikipedia.org/wiki/Precast_concrete
- [3] Precast Concrete Technology
- [4] www.pessi.in/pdf/Precast-%20A%20Competitive%20Advantage.pdf
- [5] Precast technology: The latest for quality of construction - The
[...https://economictimes.indiatimes.com/precasttechnology-the-latest.../21163272.cm](https://economictimes.indiatimes.com/precasttechnology-the-latest.../21163272.cm)

PRECAST CONCRETE STRUCTURES

- [1] paradigm.in/wp-content/uploads/2015/01/5-PRECAST.pdf
- [2] Precast Concrete Advantages versus Site-Cast Concrete

tconcrete/advantages.html

The...<https://www.concretenetwork.com/precas>



Fig: ARTIFICIAL READYMADE WALL



Fig: ARTIFICIAL READYMADE BEAMS AND COLUMNS



Fig: ARTIFICIAL READYMADE BUILDING WALL



Fig: ARTIFICIAL READYMADE BUILDING WALL WITH INHELD WINDOW



Fig: ARTIFICIAL READYMADE ARRANGEMENT OF BEAMS AND COLUMNS

THE USE OF PRECAST CONCRETE SYSTEMS IN THE ...

- [1] www.iitk.ac.in/nicee/wcee/article/14_05-06-0028.PDF
- [2] state of the art : research and application of precast/ prestressed ...
- [3] www.iitk.ac.in/nicee/wcee/article/14_05-03-0001.PDF
- [4] application of high-rise precast prestressed concrete buildings in high ...
- [5] www.iitk.ac.in/nicee/wcee/article/2191.pdf
- [6] ACI Innovation Task Group 5. 2008. Acceptance criteria for special unbonded post-tensioned precast structural walls based on validation testing and commentary (ACI ITG-5.1 M-07). American Concrete Institute, Farmington Hills, MI.
- [7] Becker, J.M., Llorente, C. & Mueller, P. 1980. Seismic response of precast concrete walls. *Earthquake Engineering & Structural Dynamics*, 8(6): 545-564.
- [8] Crisafulli, F.J., Restrepo, J.I. & Park, R. 2002. Seismic design of lightly reinforced precast concrete rectangular wall panels. *PCI Journal*, 47(4): 104-121.
- [9] Hiraishi, H. 1984. Evaluation of shear and flexural deformation of flexural type shear walls. *Bulletin of the New Zealand National Society for Earthquake Engineering*, 17(2):135-144.
- [10] PCI Industry Handbook Committee 2010. *PCI Design Handbook: Precast and Prestressed Concrete*. Prestressed Concrete Inst, 7th Edition, Chicago, IL.
- [11] SESOC Interim Design Guidance. 2013. *Design of conventional structural systems following the Canterbury earthquakes*. Version No.9, Structural Engineering Society of New Zealand.